


METER BOX DETAIL



VAULT DETAIL

- 1. METER BOXES AND UTILITY VAULTS IN SIDEWALKS SHALL BE PERPENDICULAR TO AND ADJACENT WITH THE BACK OF CURB, AND SHALL BE FLUSH WITH TOP OF SIDEWALK.
- 2. METER BOXES AND UTILITY VAULTS WITHIN THE SIDEWALK AREA SHALL HAVE A BOLT DOWN COVER WITH A SLIP—RESISTANT FINISH, COVER SHALL BE BOLTED DOWN WITH 5 SIDED BOLTS, TOP OF BOLTS SHALL BE FLUSH WITH THE TOP OF COVER.

REVISIONS	CITY OF IRVINE	STANDARD PLAN No.
	METER & VAULT COVER DETAIL	220
	Wh Cauco	
	Approved by: Mark L. Carroll R.C.E. 31515 City Engineer Date: 03-19-2009	Sheet 1 of 1